

# ADA Upgrade of Bedford Park Blvd. Station/ Concourse Line (BMT)/ Borough of the Bronx - CONTRACT A-37110



Garg Consulting Services, Inc.

This project is a \$15.7 Million upgrade of the Bedford Park Boulevard Station on the IND Concourse Line in the Bronx in order to bring the station into ADA compliance. Major work elements include the installation of an elevator from the street level to the unpaid side of the full-time mezzanine, the installation of two elevators between the paid side of the upper mezzanine and the platform levels, construction of two new elevator machine rooms, reconfiguration of some of the existing station back-of-house spaces to allow for the introduction of the elevators and machine rooms, relocation of existing street utilities, removal of out-of-service staircases between the lower mezzanine and the platform levels, and the installation of a new bus slab. The project has been scheduled to be completed in twenty-six (26) months and due for commissioning on June 16, 2020.



Garg is providing field mechanical engineering services. Garg staff has been deployed to supervise, inspect, provide responses to RFIs, review of documents and submittals for conformance to the NYCT requirements, coordinate, follow-up, provide input and implement in their respective areas of responsibilities during shop drawing submittal review and construction as well as coordinating this work with other ongoing NYCT, NYC, and private contracts that may impact this project, including night and weekend work as the construction schedule dictates.

Garg staff has been performing daily surveillance and inspections to verify that the work of the Construction Contractor is being completed in accordance with the requirements of the construction contract documents, approved shop drawings, and catalog cuts. Staff prepares daily inspection reports showing the Construction Contractors' total labor force and, by specific trade, the location of the construction activities, hours of work, special conditions, equipment used, and the actual work being performed.

Organization Name	Location	Project Duration			Dollar Amount	Prime/Sub-Consultant
		Contract Date	Start Date	Completion Date	Project Cost	Sub-Consultant
MTA-NYCT	Brooklyn, NY	05/15/2018	2018	2019	\$15.7 Million	